



RAJA PEARY MOHAN COLLEGE

1, Acharya Dhruba Pal Road,

Uttarpara, Hooghly, West Bengal, Pin- 712 258.

Ph (033)2663-0191, Fax (033) 26634155

Website : www.rpmcollege.org, e-mail : rajupearymohancollege@gmail.com

Ref.: _____

Date: 19.06.2017

Tender Notice

Properly sealed tenders are invited, from eligible, licensed and experienced vendors having official documents, for the following works. Sealed tenders should be dropped in the College Tender box to be found near the Principal's Chamber.

* Last date and time of submission of sealed tenders: 3 rd July, 2017, 4P.M.

** Date of completion of the works for gym equipments - 21 days from the date of Work Order.


*** Date of completion of the work for civil work 30 days from the date of Work Order.

**** Eligibility criteria, vendors must have trade license, vat registration, Pan Card, I.T. Return document and at last one year experience n such work

Gym Equipments:

Civil work: Repairing and up-gradation Teachers' Room of Floor Tiles, brick works etc.

Civil work: Renovation and up-gradation of existing premises of students' canteen.



Teacher-in-Charge
Raja Peary Mohan College
Uttarpara, Hooghly

Teacher-in-Charge
Raja Peary Mohan College
Uttarpara, Hooghly

E-Tendering in respect of grant from RUSA by Raja Peary Mohan College
SUBJECT: Equipments for Students Gymnasium under the head CREATION OF NEW FACILITIES

ITEMS WISE BOQ

Tender Inviting Authority: Teacher-in-Charge, RAJA PEARY MOHAN COLLEGE, UTTARPARA

Name of Work: Purchase for Equipments of Students Gymnasium

Contract No: Ref No: RPMC/RUSA/Equipments-Gym/156 dated 10/03/2017


Bidder Name :

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

2	Multi - Functional Gym MFG aims at providing full exercise of each body	1.00	1	178000.00	178000.00	INR One Lac Seventy Eight Thousand Only.
3	Exercise Bike Console : Single Window LCD Structure: 100% Commercial Tubular Construction	1.00	1	26000.0	26000.00	INR Twenty Six Thousand Only.
4	Elliptical Cross Trainer Make: Pro Bodyline Digital Multi Coloured back-lit LCD	1	1	74000.00	74000.00	INR Seventy Four Thousand Only.
5	DUMBELLS (HEX) Available Size : 2.5,5,7.5,10,12.5,,15,17.5,20 and 20KG	50.00		150.00	7500.00	INR Seven Thousand Five Hundred Only.
6	Weight Lifting Plates Round Steering Colour 28mm bore Available Size : 2.5, 5,7.5,10,15 and 20kg	1.00		3000.00	3000.00	INR Three Thousand Only.
7	Chrome Weight Lifting Rods	1.00		3000.00	3000.00	INR Three Thousand Only.
8	Sit Up Bench	1.00		6500.00	6500.00	INR Six Thousand Five Hundred Only.
9	Cable Cross Over	1.00		54000.00	54000.00	INR Fifty Four Thousand Only.
10	Exercise Yoga Mat 4mm	10.00		500.00	5000.00	INR Five Thousand Only.
11	GYM BALL	2.00		1000.00	2000.00	INR Two Thousand Only.
12	PUSH UP BAR	3.00		700.00	2100.00	INR Two Thousand One Hundred Only.
Total in Figures					361100.00	INR Five Lac Twenty Thousand One Hundred Only.
				ADD VAT @ 14.5%	52359.50	
Quoted Rate in Figures				SELECT	413459.50	INR Five Lac Ninety Five Thousand Five Hundred Fourteen and Fifty Paise Only.
Quoted Rate in Words				INR Five Lac Ninety Five Thousand Five Hundred Fourteen and Fifty Paise Only.		

Bidders are requested to submit maximum admissible discount they are ready to give on the printed price of the Equipments of Students Gymnasium


 Teacher-in-charge
 Raja Peary Mohan College
 Uttarpara, Hooghly.

E-Tendering in respect of grant from RUSA by Raja Peary Mohan College
SUBJECT: Existing premises for Students Canteen Cafeteria under the head CREATION OF NEW FACILITIES

ITEMS WISE BOQ

Tender Inviting Authority: Teacher-in-Charge, RAJA PEARY MOHAN COLLEGE, UTTARPARA

Name of Work: Renovation & up-gradation existing premises for Students Canteen Cafeteria

Contract No: Ref No: RPMC/RUSA/Renovation & up-gradation Students Canteen Cafeteria /0161 dated 10/03/2017.


Bidder Name :

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER	TEXT	NUMBER	TEXT	NUMBER	NUMBER	TEXT
Sl. No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT With Taxes	TOTAL AMOUNT In Words
1	Dismantling artificial stone flooring upto 50m.m. thick by carefully chiselling without damaging the base & removing rubbish as directed within a lead of 75 Mt.	68.25	Sq.M.	23.0	1569.75	INR One Thousand Five Hundred Sixty Nine and Seventy Five Paise Only
2	Supplying and laying true to line and level vitrified tiles of approved brand (size not less than 600mm X 600mm X 10mm thick) in floor skirting etc. set in 20 mm sand cement mortar (1:4) and 2 mm thick cement slurry back side of tiles using cement @ 2.91kg./sqM or using polymerised adhesive (6 mm thick layer applied directly over finished artificial stone floor/Mosaic etc without any backing course) last after application slurry using 1.75kg of cement per sqM below mortar only, joints grouted with admixture of white cement and colouring pigment to match with colour of tiles/epoxy grout materials of approved make as directed and removal of wax coating of top surface of tiles with warm water and polishing the tiles using soft and dry cloth upto mirror finish complete including the cost of materials, labour and all other incidental charges complete true to the manufacturer's specification and direction of Engineer-in-Charge. (White cement, synthetic adhesive and grout material to be supplied by the contractor. i) With application: slurry @ 1.75 kg/ Sq.m sand cement mortar (1:4) & 2mm thick cement slurry at back side of tiles, 0.2 kg/ Sq.m white cement for joint filling with pigment. ii) Light Colour	69.75	Sqm	1456.00	101556.00	INR One Lac One Thousand Five Hundred Fifty Six Only
3	125 mm. thick brick work with 1st class bricks in cement mortar (1:4)	8.12	Sqm.	772.0	6268.64	INR Six Thousand Two Hundred Sixty Eight and Sixty Four Paise Only
4	Plaster (to wall, base, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking. (i) With 1:6 cement mortar. (ii) 20 mm thick plaster	66.45	Sqm	178.00	11828.10	INR Eleven Thousand Eight Hundred Twenty Eight and Ten Paise Only
5	Cleaning the walls and ceiling by scraping, sand papering and smoothening down the surface including putting.	825.42	Sqm	18.00	14857.56	INR Fourteen Thousand Eight Hundred Fifty Seven and Fifty Six Paise Only
6	Applying interior grade Acrylic Primer of approved quality and brand on plastered or concrete surface old or new surface to receive Distemper/ Acrylic emulsion paint. including scraping and preparing the surface thoroughly, complete as per manufacturer's specifications and as per direction of the E.C. (a) One Coat. (i) Water based interior grade Acrylic Primer	825.42	%Sqm	3333.00	27511.25	INR Twenty Seven Thousand Five Hundred Eleven and Twenty Five Paise Only
7	Acrylic Distemper to interior wall, ceiling with primer (as per manufacturer's specification) including cleaning and smoothening of surface. Two Coats	825.42	Sqm	76.00	62731.92	INR Sixty Two Thousand Seven Hundred Thirty One and Ninety Two Paise Only
Total in Figures					226323.22	INR Two Lac Twenty Six Thousand Three Hundred Twenty Three and Twenty Two Paise Only.
					6789.70	
					233112.92	INR Two Lac Thirty Three Thousand One Hundred Twelve and Ninety Two Paise Only.
Quoted Rate in Figures						
SELECT						
Quoted Rate in Words						INR Two Lac Thirty Three Thousand One Hundred Twelve and Ninety Two Paise Only

Bidders are requested to submit maximum admissible discount they are ready to give on the printed price of the Repairing & Renovation Students Canteen Cafeteria


 Teacher-in-charge
 Raja Peary Mohan College
 Uttarpara, Hooghly.

E-Tendering in respect of grant from RUSA by Raja Peary Mohan College

**SUBJECT: Renovation & up-gradation of existing facilities for staff room/Teachers' Room under the head
CREATION OF NEW FACILITIES**

ITEMS WISE BOQ

Tender Inviting Authority: Teacher-in-Charge, RAJA PEARY MOHAN COLLEGE, UTTARPARA

Name of Work: Renovation & up-gradation of existing facilities for staff room/Teachers' room of floor tiles,brick work etc.

Contract No: Ref No: RPMC/RUSA/Repairing & Upgradation Teachers' Staff Room/0159 dated 10/03/2017


Bidder Name :

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevant columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	NUMBER #	TEXT #	NUMBER #	NUMBER #	TEXT #
Sl. No.	Item Description	Quantity	Units	Estimated Rate	TOTAL AMOUNT With Taxes	TOTAL AMOUNT In Words
1	2	4	5	6	54	55
1	Dismantling artificial stone flooring upto 50mm. thick by carefully chiselling without damaging the base & removing rubbish as directed within a lead of 75 Mt.	55.23	Sq.M.	23.0	1270.29	INR One Thousand Two Hundred Seventy and Twenty Nine Paise Only
2	Supplying and laying true to line and level vitrified tiles of approved brand (size not less than 600 mm X 600 mm X 10 mm thick) in floor, skirting etc. set in 20 mm sand cement mortar (1:4) and 2 mm thick cement slurry back side of tiles using cement @ 2.91Kg/sqM or using polymerised adhesive (6 mm thick layer applied directly over finished artificial stone floor/Mosaic etc without any backing course) laid after application slurry using 1.75 Kg of cement per sqM below mortar only, joints grouted with admixture of white cement and colouring pigment to match with colour of tiles / epoxy grout materials of approved make as directed and removal of wax coating of top surface of tiles with warm water and polishing the tiles using soft and dry cloth upto mirror finish. complete including the cost of materials, labour and all other incidental charges complete true to the manufacturer's specification and direction of Engineer-in-Charge.(White cement, synthetic adhesive and grout material to be supplied by the contractor. (i) With application slurry @ 1.75 kg/ Sq.m, 20 mm sand cement mortar (1:4) & 2 mm thick cement slurry at back side of tiles, 0.2 kg/ Sq.m white cement for joint filling with pigment, B) Light Colour.	56.89	Sqm	1456.00	82831.84	INR Eighty Two Thousand Eight Hundred Thirty One Only and Eighty Four Paise Only.
3	125 mm. thick brick work with 1st class bricks in cement mortar (1:4)	10.25	Sqm.	772.0	7913.00	INR Seven Thousand Nine Hundred Thirteen Only
4	Plaster (to wall, floor, ceiling etc.) with sand and cement mortar including rounding off or chamfering corners as directed and raking (i) With 1:6 cement mortar (b) 20 mm thick plaster	98.12	Sqm	178.00	17465.36	INR Seventeen Thousand Four Hundred Sixty Five and Thirty Six Paise Only
Total in Figures					109480.49	INR One Lac Nine Thousand Four Hundred Eighty and Forty Nine Paise Only.
					Contingency @ 3%	3284.41
Quoted Rate in Figures					Grand Total	112764.90
Quoted Rate in Words					SELECT	INR One Lac Twelve Thousand Seven Hundred Sixty Four and Ninety Paise Only.

Bidders are requested to submit maximum admissible discount they are ready to give on the printed price of the Repairing & Upgradation Teachers' Staff Room


Teacher-in-charge
Raja Peary Mohan College
Uttarpara, Hooghly.